

## TWELVE POINT CENTRAL-AIR PRECISION TUNE-UP

1. Check and clean outdoor condenser coil
  2. Check and clean indoor evaporative coil
  3. Check motor voltage and amperage
  4. Check and adjust blower components
  5. Check and clean condensate drain
  6. Check operating pressure for proper refrigerant charge
  7. Verify 20 degree delta between intake and discharge air
  8. Check all safety controls
  9. Change filters
  10. Calibrate thermostat
  11. Check starting components
  12. Check amp draw on outdoor condenser fan, contacts, relays and wiring connections
-